

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-21566-00-00  
Spot: NESENW Sec/Twnshp/Rge: 2-18S-13W  
3630 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: TINDALL Well #: 2  
County: BARTON Total Vertical Depth: 3325 feet

Operator License No.: 30886  
Op Name: THOMAS, JOHN R. DBA VAMCO OPER  
Address: 265 AVENUE K  
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3317		150 SX
SURF	8.625	262		265 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/22/2014 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3409

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 12 sx gel and 500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/23/2014 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1400', 715' and 300'. Ran tubing to 3055' and pumped 12 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1496' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 698' and pumped 75 sx cement w/200 # hulls and no returns. Shut down for the day. 07/23/2014- Ran tubing to 897'. Tagged cement and pulled 1 joint of tubing. Circulated cement to surface on casing w/90 sx cement 3%CC. Pulled tubing. Tied to casing and circulated cement to surface on surface pipe w/75 sx cement.

GPS: 38.51772 -098.73037

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

KCC WICHITA  
AUG 07 2014  
RECEIVED

District: 04

Signed Bruce Rodie  
8.18.14 CKM (TECHNICIAN) (M)

JUL 30 2014