

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21262-00-00  
Spot: SESE Sec/Twnshp/Rge: 2-29S-10W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease Name: HAUSER Well #: 1  
County: KINGMAN Total Vertical Depth: 2627 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2623	1700	75 SX
SURF	8.625	335		300 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/05/2014 12:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVE BRADY Company: QUALITY WELL SERVICE Phone: \_\_\_\_\_

Proposed Plugging Method: 25 SXS ON BOTTOM, 35 SXS @ 1500', 35 SXS @ 1000', CIRC 385' TO 0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/05/2014 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

PULLED ROD & TUBING FROM WELL. PUMP 25 SXS CEMENT 100# HULLS TO CLOSE PERFS. DISPLACED PLUG TO 2000' SI PRESSURE 1000#. LET SET OVERNITE, RECOVERED 1700' OF 5 1/2" CASING. PULLED CASING TO 1500', SPOTTED 35 SXS CEMENT. PULLED CASING TO 1000', SPOTTED 35 SXS CEMENT. PULLED CASING TO 380' CIRC CEMENT TO SURFACE WITH 135 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
2557	2562	CSG	


KCC WICHITA  
AUG 08 2014  
RECEIVED

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

District: 02

Signed



8.18.14 CKM

(TECHNICIAN)