

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21349-00-00  
Spot: NWNWSESW Sec/Twnshp/Rge: 2-29S-10W  
1096 feet from S Section Line, 1544 feet from W Section Line  
Lease Name: ALBERS Well #: 1  
County: KINGMAN Total Vertical Depth: 2605 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2600		126 SX
SURF	8.625	313		300 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/30/2014 12:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: \_\_\_\_\_

Proposed Plugging Method: 25 SXS ON BOTTOM. 35 SXS @ 1500', 35 SXS @ 1000', CIRC 350'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/01/2014 4:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED 100# HULLS & 25 SXS CEMENT DOWN 4 1/2" CASING & DISPLACED TO 2200'. REC'D 1730 CASING & PULLED TO 1500' WHERE 35 SXS CEMENT WAS SPOTTED. PULLED CASING TO 1000', SPOTTED 35 SXS CEMENT. PULLED CASING TO 350' CIRCULATED CEMENT TO SURFACE WITH 125 SXS.

Perfs:

Top	Bot	Thru	Comments
2544	2550	CSG	

KCC WICHITA  
AUG 08 2014  
RECEIVED

Remarks: QUALITY WELL SERVICE. COMMON CEMENT.

Plugged through: CSG

District: 02

Signed [Signature]  
8-18-14 CKM (TECHNICIAN)

JK