

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21314-00-00
Spot: N2NWNW Sec/Twnshp/Rge: 22-30S-34W
4950 feet from S Section Line, 4620 feet from E Section Line
Lease Name: GRACE Well #: 22
County: HASKELL Total Vertical Depth: 5916 feet

Operator License No.: 8767
Op Name: THE TREES OIL COMPANY
Address: 3552 E DOUGLAS
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5655		WITH 2 SX CMT
PROD	5.5	5966	1040	WITH 455 SX CMT
SURF	8.625	1585		WITH 675 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/10/2014 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: SET CIBP @ 5655' WITH 2 SX CMT. PLUG AT 1600' WITH 12 SX GEL & 50 SX CMT. PLUG AT 620' WITH 40 SX CMT. PLUG AT 320' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 07/10/2014 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 5655' WITH 2 SX CMT. 1ST PLUG AT 1620' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 620' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5705	5709		

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 05 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed



8-18-14 CKM

(TECHNICIAN)

RECEIVED
JUL 28 2014
KCC DODGE CITY 

