

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21025-00-00
Spot: NESWSENW Sec/Twnshp/Rge: 27-28S-8W
3074 feet from S Section Line, 3591 feet from E Section Line
Lease Name: YOUNG Well #: 1
County: KINGMAN Total Vertical Depth: 4092 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4085		100 SX
SURF	8.625	236		185 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/14/2014 12:00 PM
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.
Proposal Rcvd. from: TRACY BLACK Company: STEVE'S WELL SERVICE, INC. Phone: (316) 215-1873

Proposed Plugging Method: BJ Hope, KCC Field Rep on 6/18/14: 35 sx Class A 2% cc down tubing to bottom of tubing at 3856'. Cut tubing from 1200' plug of 35 sx Class A 2% cc, Upper plug @ 280', circ. casing full of cement

Plugging Proposal Received By: B. J. HOPE WitnessType: PARTIAL
Date/Time Plugging Completed: 07/14/2014 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

7/9/14 PUMPED 25 SXS CEMENT DOWN TUBING @ 3775', SHOT TUBING OFF. CAME UP TO 2015' PUMPED 35 SXS CEMENT (CASING LEAK). 1829' TUBING STUCK COMING OUT OFF HOLE, COULD NOT GET TUBING LOSE. CASING HAD BEEN SQUEEZED @ 1560' AND 622' COVERING SALT PLUGS. SHOT 4 SHOTS AT 280', RAN IN TOP OF FLUID 1130' PUMPED 190 SXS CEMENT, NO RETURNS, OUT OF CEMENT. 7/10/14 TAGGED TOC @ 1530', FLUID AT 1100. 7/11/14 PUMPED 85 SXS CEMENT 3% CC TAGGED AFTER 2 HOURS, NO CHANGE, PUMPED 165 SXS CEMENT LET SET OVER WEEKEND. 7/14/14 TAGGED TOC @ 1150', PUMPED 85 SXS CEMENT DOWN CASING WITH 150 LBS POLY FLAKE, PRESSURED UP, PUMPED 65 SXS CEMENT BACKSIDE CASING CIRCULATED TO SURFACE. 7/16/14 CUT HEAD OFF CEMENT STILL AT SURFACE, WELDED PLATE OVER SURFACE PIPE.

Perfs:

Top	Bot	Thru	Comments
4085	4092		

KCC WICHITA

Remarks: CONSOLIDATED OUT OF ELDORADO TICKET #48582. JUNK IN HOLE.

JUL 25 2014

Plugged through: CSG

RECEIVED

District: 02

Signed B. J. Hope
8-18-14 (TECHNICIAN)

✓ SK