

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20549-00-00  
Spot: NWNE Sec/Twnshp/Rge: 12-18S-32W  
4480 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: SCHOWALTER ACCT II Well #: 5  
County: SCOTT Total Vertical Depth: 4640 feet

Operator License No.: 31251  
Op Name: WABASH ENERGY CORPORATION  
Address: RR # 1 BOX 180A PO BOX 595  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4629	0	WITH 385 SX CMT
SURF	8.625	207		WITH 170 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/07/2014 9:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Revd. from: LARRY WHITMER Company: WABASH ENERGY Phone: (618) 943-6451

Proposed Plugging Method: PUMP 30 SX CMT WITH 150# HULLS ON BOTTOM. FILL WITH CMT FROM 2400' TO 0'. CHECK ANNULS.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/07/2014 9:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

7/7/14: PUMP 150# HULLS & 30 SX CMT TO 4568'. PUMP 45 BBL SPACER. PUMP 170 SX 60/40 POZMIX 4% GEL & 60 SX CLASS A CMT TO 2500'. HOLE DID NOT LOAD. WAIT 15 MINUTES & PUMP AN ADDITIONAL 40 SX CLASS A CMT. HOLE DID NOT LOAD. 7/10/14: CHECK TOC IN 5 1/2" AT 1200'. FILL CASING TO 0' WITH 125 SX CMT. PUMP 10 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
4566	4568		SPF

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 4% GEL & CLASS A CMT BY SWIFT SERVICES.


AUG 05 2014

Plugged through: CSG


CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed

  
B.18.14 CCM (TECHNICIAN)

RECEIVED  
JUL 17 2014  
KCC DODGE CITY

  
Form CP-2/3