

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20809-00-01
Spot: S2SWSESE Sec/Twnshp/Rge: 6-9S-16W
230 feet from S Section Line, 990 feet from E Section Line
Lease Name: BROWN OWWO Well #: 1
County: ROOKS Total Vertical Depth: 3350 feet

Operator License No.: 33759
Op Name: WINELAND OIL - LLC
Address: 3704 THUNDERBIRD DR
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3344		100 SX
SURF	8.625	206		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/05/2014 8:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JEFF CRAWFORD Company: NAE, INC. Phone: (830) 370-1500

Proposed Plugging Method:
Cleaned out iron sulfide to 3134'.
Top LKC perforation 3050'.
No upper pipe protection.

Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/05/2014 2:50 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes each at 1700', 1200' and 750'. Ran tubing back to 3114'. Swift Services pumped 100 sx cement w/300 # hulls. Pulled tubing to 1750' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 750' and pumped 55 sx cement w/100 # hulls. Circulated cement. PTOH. Squeezed 45 sx cement. Maximum pressure 500 psi. Shut in pressure 400 psi. Bled pressure off and topped 4 1/2" casing w/10 sx cement. Checked backside and it was full of cement.

GPS: 39.29336 -09914472

Perfs:

Top	Bot	Thru	Comments
3071	3320		

Received
KANSAS CORPORATION COMMISSION

Remarks: SWIFT SERVICES

Plugged through: TBG

AUG 14 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Richard Williams
8-18-14 CKM (TECHNICIAN) CM

AUG 07 2014