

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-033-20505-0008

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Slawson, Donald C. Oil Producer

Complete Address 200 Douglas Bldg, Broadway & Douglas Wichita Kansas 67202

Lease Name Barby - Harper Well No. A-1

Location 2150' FWL - 750' FSL Sec. 31 Twp. 34S Rge. 20W (East) (West)

County Comanche Total Depth 5710

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Slawson Drilling Co. Inc.

Address _____ License No. _____

Operation Completed: Hour: 9:30 PM Day: 28 Month: October Year: 1981

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

The stone coral was topped at 1128'. There is 85' of ^{20"} conductor pipe cemented from top to bottom. There is 833' of 8 5/8" surface casing cement circulated. 1st plug 1050' after circulating for 10 min with heavy mud then pumped 50 bbls to 1050'. 2nd plug pushed rubber plug to 825' and pumped 40 bbls cement on top of rubber plug. 3rd plug 40' to 0' with 10 bbls cement on solid bridge. Then pumped 5 bbls in rat hole. Plugging ^{RECEIVED} completed by allied cementing out of Kiowa Kans _{STATE CORPORATION COMMISSION}

NOV 2 1981
11-2-81

CONSERVATION DIVISION

Wichita, Kansas

I hereby certify that the above plugging instructions were stated INVOICED _____

Signed: Paul Lubbe
Conservation Division Agent

D 11-24-81
NO. 8474-W