

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED  
STATE CORPORATION COMMISSION  
AUG 3 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Raymond Oil Co. Inc.

Complete Address 200 W. Douglas Wichita, Ks

Lease Name Mai Well No. 1

Location NE/SW Sec. 11 Twp. 34 Rge. 20 (E) (W) W

County Gomanche Total Depth 5017

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 3:00 PM Day 1 Month 8 Year 1970

The above well was plugged as follows:

550 ft of 8 5/8 surface pipe cemented with 475 sacks. 4995 ft of  
5 1/2 long string cemented with 150 sacks. Top perf. 4758 ft. Sand  
to 4740 ft, 5 sacks cement with bailer. Pulled 4000 ft of 5 1/2. Set  
10 ft rock bridge at 350 ft, 35 sacks cement. Sand to 40 ft, 10 ft  
rock bridge, 10 sacks cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 8/3/70  
INV. NO. 2322-U