

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23191-00-00
Spot: NENE Sec/Twnshp/Rge: 14-31S-13W
697 feet from N Section Line, 678 feet from E Section Line
Lease Name: MADDIX TRUST Well #: 1-14
County: BARBER Total Vertical Depth: 4612 feet

Operator License No.: 33856
Op Name: WHITE EXPLORATION, INC.
Address: 1635 N. WATERFRONT PKWY SUITE 1
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3650		
PROD	4.5	3799	1524	WITH 400 SX CMT
SURF	8.625	234		WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/14/2014 1:30 PM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: TERRY BAIRD Company: WHITE EXPLORATION Phone: (316) 641-8906

Proposed Plugging Method: Cut 4-1/2 as low as possible (Top Cement @ 1650') Spot plug @ 640' (50 sacks Cement and 10 sacks gel). Pull up to 30' below base of Surface Casing @ 260' and set cement plug of 50 sacks of cement. Pull up to 40' and plug from 40' to surface with 20 sacks cement

Plugging Proposal Received By: STEVE PFEIFER Witness Type: PARTIAL
Date/Time Plugging Completed: 08/14/2014 4:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

BRIDGE PLUG AT 3650'. 1ST PLUG AT 658' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 250' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:


Top	Bot	Thru	Comments
3690	3693		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

Received
KANSAS CORPORATION COMMISSION
AUG 27 2014
CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed 
(TECHNICIAN)

9-2-14 cpm

RECEIVED

AUG 22 2014

KCC DODGE CITY

Form CP-2/3