

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-28035-00-00
Spot: SWSWNWNE Sec/Twnshp/Rge: 12-29S-14E
1162 feet from N Section Line, 2462 feet from E Section Line
Lease Name: FORTNER Well #: 40P
County: WILSON Total Vertical Depth: 1163 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 111 CONGRESS AVE, STE 400
AUSTIN, TX 78701

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	8	20		SX
PROD	0	0		0 SX
SURF	8	20		8 SX

Well Type: ST UIC Docket No: _____ Date/Time to Plug: 09/10/2012 8:00 AM
Plug Co. License No.: 9386 Plug Co. Name: GUS JONES CABLE TOOL SERVICE, LLC
Proposal Rcvd. from: DONALD MISSEY Company: WILSON COUNTY HOLDINGS Phone: (303) 884-3203

Proposed Plugging Method: Revised plugging procedure from well bottom: 100' cement at well bottom, water-based drilling mud plug 500' from bottom, 100' cement plug, water-based mud to 250' from well top elevation, and 250' cement plug to surface. After set, well is cut off at 4' below grade.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 09/10/2012 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to 1135' and a 25 sack cement plug placed. The cement string was raised to 635' and a 25 sack cement plug placed. The cement string was then raised to 250' and the well filled to surface with cement. The operator reported that 125 sacks of portland cement were used to plug well; gel spacers between. The well was cwy off below plow depth and the location restored.

Perfs:

RECEIVED
JUL 11 2014
KCC Chanute Dist. #3

AD

KCC WICHITA

JUL 16 2014

RECEIVED

Remarks:

Plugged through: TBG

District: 03

Signed

Alan M. Dunning
(TECHNICIAN)
9.2.14 am