

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-049-20207-00-01
Spot: SWSWNE Sec/Twnshp/Rge: 16-31S-9E
4243 feet from S Section Line, 1037 feet from E Section Line
Lease Name: REEVES Well #: AS 1
County: ELK Total Vertical Depth: 2299 feet

Operator License No.: 31119
Op Name: WOLFE, ROBERT & DEBBIE S. DBA LO
Address: BOX 241
MOLINE, KS 67353

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2260		225 SX
SURF	8.625	31		35 SX

Well Type: EOR UIC Docket No: E19323.1 Date/Time to Plug: 08/11/2014 12:00 AM
Plug Co. License No.: 3591 Plug Co. Name: C & E OIL, LLC
Proposal Rcvd. from: ROB WOLFE Company: Phone: (620) 647-3626

Proposed Plugging Method: Perforate at 500 ft. Run tubing to bottom and circulate cement to top. Pulled tubing and top off with cement.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/11/2014 8:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perforated casing at 500'. Ran 1" to 2267' and circulated cement to surface with 45 sacks of cement. Pulled 1" and hooked onto casing and squeezed 55 sacks of cement down casing at 500 psi. Shut well in with 200 psi on casing.

Perfs:

Top	Bot	Thru	Comments
2288	2299		
Received KANSAS CORPORATION COMMISSION AUG 21 2014 CONSERVATION DIVISION WICHITA, KS RECEIVED AUG 19 2014 KCC Chanute Dist. #3 DS			

Remarks: WELL WAS PLUGGED DUE TO SETTLEMENT AGREEMENT (15-CONS-043-CMSC) SIGNED WITH THE KCC.

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)

cc: uic ✓
9/2/14 cfm