

To: 1 090319
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-8

API NUMBER 15- 151-21,567-00-01-
SE NW SE, SEC. 30, T. 26 S, R. 13 W X

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588
Operator: Woodman-Iannitti Oil Company
Name & Address: P.O. Box 308
Great Bend, KS 67530

1650 feet from S section line
1650 feet from E section line
Lease Name Tobias A Well # 1
County Pratt
Well Total Depth 1463 47.54 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 434

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor White & Ellis Drilling, Inc. License Number 5420
Address P.O. Box 48848, Wichita, KS 67201-8848

Company to plug at: Hour: 6 a.m. Day: 8 Month: 9 Year: 19 93

Plugging proposal received from Judy
(company name) White & Ellis Drilling, Inc. (phone) 316-263-1102

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 910'
1st plug at 910' with 50 sx cement,
2nd plug at 460' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 8:30 a.m. Day: 8 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 910' with 50 sx cement,
2nd plug at 460' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

INVOICED

If additional description is necessary, use BACK of the STATE CORPORATION COMMISSION

I (XXXX) did not observe this plugging.

DATE 9-23-93

Signed [Signature] (TECHNICIAN) SEP 10 1993

INV. NO. 38774