

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-22315-00-00  
Spot: NESWNE Sec/Twnshp/Rge: 15-25S-31W  
335 feet from S Section Line, 1954 feet from W Section Line  
Lease Name: O'BRATE-FINNEY Well #: 5-15  
County: FINNEY Total Vertical Depth: 1217 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
COND		0		
PROD		0		
SURF		0		

Well Type: LH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/29/2014 8:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JOSE Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: SEE ACTUAL PLUGGING REPORT

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/18/2014 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

**\*\*13 DRILL COLLARS, BIT SUB & 12 1/4" PDC BIT LEFT IN HOLE\*\*** BOTTOM AT 430' & TOP OF DRILL COLLARS AT 17.5'. ATTEMPT TO RUN TBG DOWN OUTSIDE OF DRILL COLLARS. LOST CIRCULATION AT 60'. RUN 1 1/2" TBG INSIDE DRILL COLLAR TO FLOAT IN BIT SUB. CIRCULATE CLEAN. COULD NOT PUMP THROUGH BIT AT 1000#. 8/8/14 & 8/11/14: PERFORATE 24 HOLES IN DRILL COLLAR AT 415'. PUMPED 400 SX CMT. OVER DISPLACE 5 BBL WATER. 8/12/14: PUMPED 400 SX CMT THROUGH PERFS. DISPLACE WITH WATER TO 200'. 8/13/14: TAG TOC IN DRILL COLLAR AT 199'. PERFORATE 20 HOLES AT 178'. INJECTION RATE 1/2 BPM AT 1000#. 8/15/14: REPERF 44 HOLES AT 178'. INJECTION RATE 3 BPM @ 1000#. NO CIRCULATION TO SURFACE. 8/18/14: PUMPED 150 SX CMT THROUGH PERFS. OVER DISPLACE 3 BBL WATER. WAIT 3 HOURS. PUMP ANOTHER 150 SX CMT @ 1.5 BPM AT 700# TO 550#. NO CIRCULATION TO SURFACE. UNSCREW 17 1/2" DRILL PIPE SUB & CIRCULATE CMT FROM 17' TO SURFACE & TOP OUT WITH A TOTAL OF 20 SX CMT. STAYED FULL. LEFT A 2 3/8" X 7" MUD ANCHOR 4' BELOW GROUND LEVEL FOR A MARKER.

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: DP

District: 01

Signed Ken Jehlik & Stephen J. [Signature]  
(TECHNICIAN)

RECEIVED  
AUG 22 2014  
KCC DODGE CITY

Received  
KANSAS CORPORATION COMMISSION

SEP 02 2014

CONSERVATION DIVISION  
WICHITA, KS

9.5.14 CKM

Form CP-2/3