

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-01005-00-01
Spot: NESWNESE Sec/Twnshp/Rge: 9-20S-19W
1850 feet from S Section Line, 950 feet from E Section Line
Lease Name: BAKER Well #: 9-9
County: PAWNEE Total Vertical Depth: 4230 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2338		
L1	4.5	4230		WITH 450 SX CMT
PROD	5.5	4230	0	WITH 125 SX CMT
SURF	8.625	132		WITH 100 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/22/2014 8:15 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 08/22/2014 10:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

CIBP @ 2338'. JUNK IN HOLE AT 1100'. SET CIBP @ 1100' WITH 2 SX CMT. PERFORATED AT 600'. RAN TBG TO 600' & CIRCULATED CMT INSIDE 4 1/2" TO SURFACE WITH 70 SX CMT. TIED ONTO BACKSIDE AND PRESSURED TO 500# WITH NO CMT.

Perfs:

Top	Bot	Thru	Comments
2290	2321		

Received
KANSAS CORPORATION COMMISSION
SEP 02 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: TBG

District: 01

RECEIVED
AUG 26 2014
KCC DODGE CITY

Signed

Richard Lacey
(TECHNICIAN)

9.5.14 CKM

Form CP-2/3