

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21380-00-00  
Spot: NWSENESW Sec/Twnshp/Rge: 21-20S-19W  
1955 feet from S Section Line, 3288 feet from E Section Line  
Lease Name: SMITH Well #: 21-11  
County: PAWNEE Total Vertical Depth: 2460 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2230		WITH 2 SX CMT
PROD	4.5	2441	0	WITH 125 SX CMT
SURF	8.625	457		WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/22/2014 10:30 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: SET CIBP @ 2230' & 2 SX CMT. PERFORATE AT 1380'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE  
Date/Time Plugging Completed: 08/22/2014 1:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 2230' WITH 2 SX CMT. PERFORATE AT 1380'. TIED ONTO 4 1/2" AND TRIED TO ESTABLISH CIRCULATION BUT GOT NONE. PUMPED 180 SX CMT DOWN 4 1/2" (80 SX OVER CASING VOLUME). TIED ONTO BACKSIDE AND PUMPED 15 SX CMT, PRESSURING TO 500#. TOPPED OFF 4 1/2" CASING WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2358	2364		
2282	2313		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

Received  
KANSAS CORPORATION COMMISSION  
SEP 02 2014  
CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed

Richard Lacey  
(TECHNICIAN)

9.5.14 CLM

RECEIVED  
AUG 26 2014  
KCC DODGE CITY