

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21385-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 19-20S-19W  
1000 feet from S Section Line, 985 feet from E Section Line  
Lease Name: MILLER Well #: 19-16  
County: PAWNEE Total Vertical Depth: 2425 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2362		
PROD	4.5	2424	0	WITH 125 SX CMT
SURF	8.625	432		WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/22/2014 1:30 PM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: SET CIBP @ 2260' WITH 2 SX CMT. PERFORATED AT 1365'. TIED ONTO 4 1/2" AND TRIED TO ESTABLISH CIRCULATION BUT GOT NONE. PUMPED 180 SX CMT DOWN 4 1/2" (80 SX OVER CASING VOLUME). TIED ONTO BACKSIDE AND PUMPED 60 SX CMT. PRESSURED TO 500#. TOPPED OFF 4 1/2" WITH 50 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 08/22/2014 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 2260' WITH 2 SX CMT. PERFORATED AT 1365'. TIED ONTO 4 1/2" AND TRIED TO ESTABLISH CIRCULATION BUT GOT NONE. PUMPED 180 SX CMT DOWN 4 1/2" (80 SX OVER CASING VOLUME). TIED ONTO BACKSIDE AND PUMPED 60 SX CMT. PRESSURED TO 500#. TOPPED OFF 4 1/2" WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2312	2338		

Received  
KANSAS CORPORATION COMMISSION  
SEP 02 2014  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

District: 01

RECEIVED  
AUG 26 2014

Signed Michael Maier  
(TECHNICIAN)

9.5.14 CKM

KCC DODGE CITY