

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-02258-00-00  
Spot: NWNESENW Sec/Twnshp/Rge: 7-34S-14E  
3615 feet from S Section Line, 3301 feet from E Section Line  
Lease Name: BURRIS Well #: B-32  
County: MONTGOMERY Total Vertical Depth: 750 feet

Operator License No.: 35005  
Op Name: BPG CAPITAL, LLC  
Address: 100 N. COLLEGE ST., SUITE 408  
WAXAHACHIE, TX 75165

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|---------|
| PROD   | 6.25 | 0          |             | 0 SX    |
| SURF   | 10   | 0          |             | 0 SX    |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/31/2014 4:00 PM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: DAVID WILLIS Company: \_\_\_\_\_ Phone: (620) 433-2264

Proposed Plugging Method: Run 1" to bottom, gel hole, spot 20 sacks of cement, pull 1" out, perforate casing at 250', run 1" in, cement 250' to surface inside and outside of casing, pull 1" out, top off with cement, cut well head off below surface, restore location.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/31/2014 4:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Operator milled on well until they got down to 250'. They pulled mill out and ran 1" down well. They got to 548' with the 1". They gelled hole and spotted 30 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 125 sacks of cement were used to plug this well.

Perfs:

RECEIVED  
AUG 26 2014  
KCC Chanute Dist #3

DS

Received  
KANSAS CORPORATION COMMISSION  
SEP 02  
CONSERVATION  
WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]  
9.5.14 ckm  
(TECHNICIAN)