

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-03211-00-00
Spot: SEWNENE Sec/Twnshp/Rge: 16-24S-18E
4715 feet from S Section Line, 824 feet from E Section Line
Lease Name: CLINE Well #: B15
County: ALLEN Total Vertical Depth: 881 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4	856		10 SX
SURF	7	404		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/10/2014 12:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: (620)365-3111

Proposed Plugging Method: COMPANY UNIT RIH 2" TO BTM SERVICE COMPANY GELLED HOLE UP THEN PUMP 100' CEMENT PLUG PULL UP TO 500' PUMP 50' CMT PLUG PULLED UP TO 250' PUMPED CEMENT TO SURFACE. COMPANY UNIT PULLED TBG TOPPED WELL OFF. WILL RETURN LATER TO CUT SURFACE OFF BELOW PLOW DEPTH.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 07/10/2014 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran and washed 2" pipe down to TD. Mixed and pumped gel down the 2" to TD. Mixed and pumped 25 sacks of cement through the 2" pipe at TD. Pulled 2" pipe up to 500'. Spotted 10 sacks of cement at 500'. Pulled tubing up to 250'. Circulated cement from 250' to surface. Pulled the rest of the 2" tubing and topped the well off with cement. A total of 110 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
869	879		
RECEIVED SEP 02 2014 KCC Chanute Dist #3 RD Received KANSAS CORPORATION COMMISSION			

Remarks:

Plugged through: TBG

SEP 05 2014

CONSERVATION DIVISION
WICHITA, KS

District: 03

Signed

9.5.14 CKM

(TECHNICIAN)