

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-001-03218-00-00  
Spot: NWNESENE Sec/Twnshp/Rge: 16-24S-18E  
3885 feet from S Section Line, 480 feet from E Section Line  
Lease Name: CLINE Well #: C11  
County: ALLEN Total Vertical Depth: 874 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.875	835		0 SX
SURF	6.25	350		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/17/2014 12:00 AM  
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC  
Proposal Rcvd. from: REX ASHLOCK Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: 7/17/14 COMPANY SERVICE UNIT RIH 1 1/4" TBG TO 788'. ELITE CEMENT & ACIDIZE OF KANSAS PUMP 300' CEMENT PLUG @788'. SERVICE UNIT PULL TBG UP TO 500' ELITE PUMP 50' CEMENT PLUG. SERVICE UNIT PULL TBG UP TO 250' ELITE PUMP CEMENT FROM 250' TO SURFACE. SERVICE UNIT PULL ROH REST OF TBG ELITE TOP WELL OFF. WILL COME BACK AT LATER DATE CUT SURFACE OFF "BELOW PLOW DEPTH".

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed: 07/17/2014 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran and washed 1" pipe down to TD. Pumped cement down the 1" and spotted 300' cement plug at TD. Pulled 1" pipe up to 500'. Spotted 50' cement plug at 500'. Pulled tubing up to 250'. Circulated cement from 250' to surface. Pulled the rest of the 1" tubing and topped the well off with cement.

Perfs:

Top	Bot	Thru	Comments
864	874		
RECEIVED SEP 02 2014 KCC Chanute Dist. #3  RD			
Received KANSAS CORPORATION COMMISSION			

Remarks:

Plugged through: TBG

SEP 05 2014  
CONSERVATION DIVISION  
WICHITA, KS

District: 03

Signed [Signature]  
9.5.14 CPM (TECHNICIAN)