

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-19359-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 16-24S-18E
188 feet from N Section Line, 1090 feet from E Section Line
Lease Name: CLINE Well #: B19
County: ALLEN Total Vertical Depth: 920 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	903		25 SX
SURF	12	12		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/05/2014 12:00 AM
Plug Co. License No.: 5150 Plug Co. Name: COLT ENERGY INC
Proposal Rcvd. from: REX ASHLOCK Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: COMPANY UNIT RIH 2" 8RD EUE TO TD. SERVICE UNIT CIRCULATED GET TO TOP. PUMPED 300' CMT PLUG ON BTM COMPANY UNIT PULLED UP TBG TO 500' SERVICE UNIT PUMPED 50' CMT PLUG. COMPANY UNIT PULLED 2" TBG UP TO 250'. SERVICE COMPANY PUMPED CEMENT FROM 250' TO SURFACE. COMPANY UNIT PULLED REST OF 2" TBG SERVICE COMPANY TOPPED WELL OFF AT SURFACE. WILL COME BACK LATER & CUT SURFACE CSG OFF BELOW "PLOW DEPTH".

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 07/10/2014 12:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran and washed 2" pipe down to TD. Mixed and pumped gel down the 2" to TD. Spotted 300' cement plug at TD. Pulled 2" pipe up to 500'. Spotted 50' cement plug at 500'. Pulled tubing up to 250'. Circulated cement from 250' to surface. Pulled the rest of the 2" tubing and topped the well off with cement.

Perfs:

Top	Bot	Thru	Comments
903	920		

RECEIVED
SEP 02 2014
KCC Chanute Dist. #3
RD
Received
KANSAS CORPORATION COMMISSION

Remarks:

Plugged through: TBG

SEP 05 2014

CONSERVATION DIVISION
WICHITA, KS

District: 03

Signed

[Signature]
9-5-14 CKM (TECHNICIAN)