

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-29008-00-00
Spot: W2SESESW Sec/Twnshp/Rge: 30-24S-18E
330 feet from S Section Line, 2998 feet from E Section Line
Lease Name: KRAMER Well #: 1-30
County: ALLEN Total Vertical Depth: 1200 feet

Operator License No.: 33741
Op Name: ENERJEX KANSAS, INC.
Address: 2038 S. PRINCETON ST., STE B
OTTAWA, KS 66067

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	1182		185 SX
PROD	5.5	1183		
SURF	8.625	43		10 SX

Well Type: GAS UIC Docket No: Date/Time to Plug: 06/09/2013 12:00 AM
Plug Co. License No.: 34283 Plug Co. Name: WILLIS WELL SERVICE LLC
Proposal Rcvd. from: JARED HAMMOND Company: Phone: (785) 241-2228

Proposed Plugging Method: CEMENT FROM BOTTOM TO TOP PER RYAN DOOLING

Plugging Proposal Received By: RYAN DULING WitnessType: NONE
Date/Time Plugging Completed: 06/10/2013 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 5.5" casing to TD. Pumped and circulated cement from TD to surface. Pulled the 1" pipe out of the hole. Topped the well off with cement. A total of 180 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
938	940		SPF
870	872		SPF
857	859		SPF
804	806		SPF
728	730		SPF
713	715		SPF
706	709		SPF
702	704		SPF
620	622		SPF
303	307		SPF

RECEIVED

AUG 27 2014

KCC Chanute Dist. #3

RD

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

9.5.14 CKM

Form CP-2/3

AUG 29 2014

CONSERVATION DIVISION
WICHITA, KS