

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21691-00-00
Spot: NWNENWSW Sec/Twnshp/Rge: 24-30S-8W
2365 feet from S Section Line, 4465 feet from E Section Line
Lease Name: WSU Well #: 2
County: KINGMAN Total Vertical Depth: 4502 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4489		1090 SX
SURF	8.625	305		200 SX
SURF		314		

Well Type: EOB UIC Docket No: E26857.2 Date/Time to Plug: 10/27/2014 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RANDY DICK Company: QUALITY WELL SERVICE Phone: (620) 425-1000

Proposed Plugging Method: SAND TO 4220' & 5 SXS CEMENT. 35 SXS @ 1250', 35 SXS @ 800'. CIRC 350'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/21/2014 2:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

PAKER STUCK IN HOLE. PUMPED 25 SXS CEMENT, 3 SXS HULLS ON BOTTOM. SHOT TUBING 3 JOINTS ABOUT PACKER. SPOTTED 10 SXS CEMENT LAYED TUBING DOWN. CASING CIRCLED WITH CEMENT TO SURFACE. PERFED CASING AT 1250', RAN TUBING TO 1250' SPOTTED 35 SXS CEMENT. PULLED TUBING TO 800' & CIRC'D WELL BACK TO SURFACE WITH 70 SXS CEMENT. RAN 1" TUBING TO 100' & CIRCLED BACK HOLE FULL OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
4304	4331	CSG	
4270	4298	CSG	


Received
KANSAS CORPORATION COMMISSION
SEP 02 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY WELL SERVICE 60/40 -- TA'D WELL

Plugged through: TBG

District: 02

Signed



cc: uic ✓ (TECHNICIAN)

9-5-14CKM

JK