

SIDE TWO

Operator Name Timberline Oil & Gas Lease Name Strait Well# 13 SEC 28 TWP. 26 RGE. 13 East West

County Pratt

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken Yes No
 Samples Sent to Geological Survey Yes No
 Cores Taken Yes No

Formation Description
 Log Sample

Sand, clay 0-198
 Red beds, shale 198-1995
 Shale, lime 1995-4430
 Arbuckle 4430-4520

Name	Top	Bottom
Tarkio lime	2945	2978
Arbuckle	4438	4520

CASING RECORD <input type="checkbox"/> new <input type="checkbox"/> used							
Report all strings set - conductor, surface, intermediate, production, etc.							
Purpose of string	size hole drilled	size casing set (in O.D.)	weight lbs/ft.	setting depth	type of cement	# sacks used	type and percent additives
Surface	14 3/4"	10 3/4"	34#	306' KB	60/40 Poz	250	2% Gel, 3%CC
Production	7 7/8"	5 1/2"	14#	4519' KB plus	60/40 Pos ASC	200 50	5% Gilsomite 2% CC
PERFORATION RECORD				Acid, Fracture, Shot, Cement Squeeze Record			
shots per foot	specify footage of each interval perforated			(amount and kind of material used)			Depth
2	4448-56'			500 gal. 15% HCL			4448-56'
2	2967-73'			500 gal. 15% HCL			2967-73'
TUBING RECORD				Liner Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No			
Date of First Production		Producing method					
1/2/86		<input type="checkbox"/> flowing <input checked="" type="checkbox"/> pumping <input type="checkbox"/> gas lift <input type="checkbox"/> Other (explain)					
Estimated Production Per 24 Hours	Oil	Gas	Water	Gas-Oil Ratio		Gravity	
1	Bbls	0 MCF	50 Bbls	CFPB		40°	

Disposition of gas: vented
 sold
 used on lease

METHOD OF COMPLETION
 open hole perforation
 other (specify)

PRODUCTION INTERVAL

2967-73'

Duv Completed.
 Corringled