

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

Mod

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-151-21,567-00-00 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR F & M OIL CO., INC. OPERATORS LICENSE NO. 5313

ADDRESS 422 Union Center, Wichita, Kansas 67202 PHONE # (316) 262-2636

LEASE (FARM) Tobias "A" WELL NO. 1 WELL LOCATION SE NW SE COUNTY Pratt

SEC. 30 TWP. 26S RGE. 13W (E) or (W) (W) TOTAL DEPTH 4580' PLUG BACK TD -----

Check One:

OIL WELL _____ GAS WELL _____ D & A XX SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 434' CEMENTED WITH 325 SACKS

CASING SIZE ---- SET AT ---- CEMENTED WITH ---- SACKS

PERFORATED AT -----

CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE (CL)

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set 1st plug @ 890' w/50 sxs, 2nd plug @ 470'
w/40 sxs, 3rd plug @ 40' w/10 sxs, 10 sxs in rat hole, 10 sxs in mouse hole, filled wtr well w/
appx. 10 sxs, cmt. by Halliburton w/60/40 poz., 2% gel, 3% CC, plug down @ 1 PM 2-7-85.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Not required IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN February 7, 1985 1 PM

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

RECEIVED
STATE CORPORATION COMMISSION

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: MAR 07 1985

T. F. Brown PHONE # (316) 886-5863

ADDRESS P.O. Box 43, Medicine Lodge, Ks. 67104

PLUGGING CONTRACTOR Union Drilling Co., Inc. LICENSE NO. 5103

ADDRESS 422 Union Center, Wichita, Kansas 67202 PHONE # (316) 262-1872

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Ronald J. Schneider, Operator
(Operator or Agent)

DATE: March 6, 1985