

STATE OF KANSAS  
STATE CONSERVATION DIVISION  
CONSERVATION DIVISION  
130 S. MARKET, ROOM 2078  
Wichita, Kansas 67202

SEP 19 2000

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM AND FILE ONE COPY)

CONSERVATION DIVISION  
Wichita, Kansas

API # 15-009-22,987-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR VESS OIL CORPORATION KCC LICENSE # 5030  
(owner/company name) (operator's)

ADDRESS 8100 E. 22nd St. North, Bldg. 300 CITY Wichita

STATE Kansas ZIP CODE 67226 CONTACT PHONE # (316) 682-1537

LEASE Oberle WELL# 1 SEC. 36 T. 17S R. 11W (East/West)

100' N SE NE SW SPOT LOCATION/QQQQ COUNTY Barton

1750 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

2970 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET #

CONDUCTOR CASING SIZE  SET AT  CEMENTED WITH  SACKS

SURFACE CASING SIZE 8-5/8" SET AT 229' CEMENTED WITH 150 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 3260' CEMENTED WITH 125 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Arb OH 3260-63

ELEVATION 1811/1816 T.D. 3263 PBSD 3263 ANHYDRITE DEPTH 589-603  
(G.L./K.B.) (Stone Corral Formation) (driller's log)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING per KCC instructions

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? old form

If not explain why? no logs were run on well (copy of driller's log attached)

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Casey Coats PHONE (316) 682-1537

ADDRESS 8100 E. 22nd Street North, Bldg. 300 CITY/STATE Wichita, KS 67226

PLUGGING CONTRACTOR Mike's Testing & Salvage KCC LICENS 31529  
(contractor's)

ADDRESS Box 467, Chase KS PHONE # (316) 938-2943

PROPOSED DATE AND HOUR OF PLUGGING (if known?) about 2 months

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9/16/00 AUTHORIZED OPERATOR/AGENT: [Signature]  
(signature)

6/01

9/00

JK

DRILLERS' WELL LOG

DATE COMMENCED: December 20, 1982  
DATE COMPLETED: December 29, 1982

Petroleum Energy, Inc.  
OBERLE #1  
100' N of SE NE SW  
Sec. 36, T17S, R11W  
Barton County, Ks.

ELEVATION: 1816 K.B.

0 - 589' Surface soil, Shale, Red Bed  
589 - 608' Anhydrite  
608 - 2550' Lime & Shale  
2550 - 2583' Lime  
2583 - 2598' Shale & Sand  
2598 - 2855' Lime  
2855 - 2859' Shale  
2859 - 2874' Lime & Shale  
2874 - 2885' Lime  
2885 - 2967' Shale  
2967 - 2982' Lime & Shale  
2982 - 3259' Lime  
3259 - 3263' Dolomite  
3263' RTD

FORMATION DATA

Anhydrite	589'
Howard	2550'
Severy	2583'
Topeka	2598'
Heebner	2855'
Toronto	2874'
Douglas	2885'
Br. Lime	2967'
Kansas City	2982'
Arbuckle	3259'
RTD	3263'


Surface pipe: Set used 8-5/8",  
28# pipe @229' w/150 sacks 60/40  
pozmix, 2% gel 3% cc.

Production pipe: Set new & used  
5 1/2", 14# @3260 1/2' w/125 sacks  
50/50 pozmix, 2% gel 10% salt  
w/ 10 Bbls. salt flush.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Leonard Williamson of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

  
\_\_\_\_\_  
Leonard Williamson

Subscribed and sworn to before me this 11<sup>th</sup> day of January 1983.

My Comm. Expires:

4-29-86

  
\_\_\_\_\_  
Notary Public



## Kansas Corporation Commission

Bill Graves, Governor   John Wine, Chair   Cynthia L. Claus, Commissioner   Brian J. Moline, Commissioner

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Vess Oil Corporation  
8100 E. 22nd N. Bldg. 300  
Wichita, KS 67226

September 21, 2000

OBERLE #1  
API 15-009-22987-00-00  
1750 S 2970 W  
N2SENE SW 36-17S-11W  
BARTON COUNTY

Dear Casey Coats:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #4  
2301 E. 13th  
Hays, KS 67601  
(785) 625-0550

Sincerely,  
Handwritten signature of David P. Williams in cursive.

David P. Williams  
Production Supervisor