

4-020105

FEB - 9 2000

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-24, 601-00-00
CONSERVATION DIVISION
Wichita, Kansas
SW SW SE /4 SEC. 30, 17 S, 11 W
330 feet from S section line
2310 feet from E section line

Operator license# 7383
Operator: Grady Bolding Corporation

2/4/00

Lease: Schneweis Grace Well # 1
County: Barton 111, 15

Address: P.O. Box 486
Ellinwood, Kansas 67526

Well total depth 3420 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 289 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 2:00 P.M. Day: 4 Month: February Year: 2000

Plugging proposal received from: Monte Andrews

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Ordered out 200 sxs 60/40 pozmix - 10% gel - 500# hulls.
Prod perms at 3267' - 3272'; 3303' - 3308'; 3324' - 3328'.
Shot casing off at 2340'.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 4:30 P.M., Day: 4 Month: February, Year: 2000

Actual plugging report: 8 5/8" set at 289' w/165 sxs. 5 1/2" set at 3419' w/150 sxs cmt.
Sanded off to 3250' and topped with 5 sxs cement with dump bailer.
Shot casing off at 2340'.

Pulled casing to 1425' - tied onto and spotted 100 sxs with 300# hulls.
Pulled casing to 700' - tied onto and pumped 40 sxs with 100# hulls.
Pulled casing to 200' - tied onto and circulated cement with 60 sxs cement and 100# hulls.
Pulled casing out of the hole.
Hole standing full of cement.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD
Bottom plug(in place): YES CALC NO
Plugged through TUBING , CASING .
Anhy.plug: YES NO
Dakota plug: YES NO
Elevation: 1833 GL

I did[] / did not[] observe the plugging.

[Signature]
(agent)

INVOICED
DATE 2/9/00
INV. NO. 06239

(R)