

1 020217

2-24

135 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-189-21,306-00-00  
SE NW SE, SEC. 12, T 33 S, R 39 (N/E)

TECHNICIAN'S PLUGGING REPORT

Operator License # 5598

Operator: APX Corporation  
Name & Address: P.O. Box 351  
Liberal, KS 67905-0351

1390 feet from S section line  
1390 feet from E section line

Lease Name Holcomb "C" Well # 1H  
County Stevens 56.75

Well Total Depth 1746 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 521

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Gabbert-Jones, Inc. License Number 5842

Address 333 East English, Suite 215, Wichita, KS 67202

Company to plug at: Hour: 2 p.m. Day: 24 Month: 2 Year: 19 89

Plugging proposal received from Jim Barlow

(company name) APX Corporation (phone) 316-624-6253

were: to fill hole with heavy mud and spot cement through drill pipe

Drill pipe stuck at 1741', backed off at 1227', still stuck, backed off at 965'.

1st plug at 930' with 40 sx cement, 2nd plug at 540' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part X None \_\_\_\_\_

Operations Completed: Hour: 3:30 p.m. Day: 24 Month: 2 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 900' with 40 sx cement,

2nd plug at 540' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Left 18 collars and 9 joints pipe in hole, sanded in, stuck.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 3-6-89

INV. NO. 24054

2-24

Signed Jim Barlow  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 03 1989

3-3-89

CONSERVATION DIVISION  
Wichita, Kansas

NOTICE OF INTENTION TO DRILL  
HUGOTON INFILL

Starting Date 2 17 89  
month day year

API Number 15- 189-21,306

OPERATOR: License # 5598  
Name APX Corporation  
Address P. O. Box 351  
City/State/Zip Liberal, Kansas 67905-0351  
Contact Person Jim Barlow  
Phone (316) 624-6253

SE Sec. 12 Twp. 33 S. Rg. 39 W  
1390 Ft. from South Line of Section  
1390 Ft. from East Line of Section

CONTRACTOR: License # 5842  
Name Gabbert-Jones, Inc.  
City/State Wichita, Kansas 67202

NOTE: Attach acreage attribution plat locating both Chase (Hugoton) wells  
Total number of acres attributed to unit 624

Well Drilled as:  New  Recompletion  OWWO  
Projected Total Depth 2840 feet  
Formation Hugoton

Nearest producing well from  
same common source of supply 2711 feet

If OWWO or Recompletion: old well info as follows:  
Operator \_\_\_\_\_  
Well Name \_\_\_\_\_  
Comp Date \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Nearest lease or unit boundary line 1250 feet  
County Stevens

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.  
Date 2/7/89 Signature of Operator or Agent Jim Barlow Title Drilling Supervisor

Lease Name HOLCOMB "C" Well # 11  
Ground surface elevation 3200 feet MSL

Depth to bottom of fresh water 460 400  
Depth to bottom of usable water 460 500

Surface pipe by Alternate: 1 X 2  
Surface pipe planned to be set 500 520'

For KCC Use:  
Conductor Pipe Required \_\_\_\_\_ feet; Minimum Surface Pipe Required 520' feet per Alt. (1) Q  
This Authorization Expires 8-8-89 Approved By LKM 2-8-89

EFFECTIVE DATE: 2-13-89

10/86

*8 5/8 " x 521*

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 05 1989  
CONSERVATION DIVISION  
Wichita, Kansas

PUSHER Jim Barlow  
TD 1746 FORMATION \_\_\_\_\_  
SURFACE PIPE 8 5/8 @ 521  
ANHYDRITE \_\_\_\_\_ ELEVATION \_\_\_\_\_  
STARTING TIME & DATE \_\_\_\_\_  
COMPLETION TIME & DATE \_\_\_\_\_  
1st PLUG @ 930 FT. W/ 40 SX  
2nd PLUG @ 540 FT. W/ 50 SX  
3rd PLUG @ 40 FT. W/ 10 SX  
4th PLUG @ \_\_\_\_\_ FT. W/ \_\_\_\_\_ SX  
RAT HOLE CIRCULATED W/ 15 SX  
MOUSE HOLE CIRCULATED W/ \_\_\_\_\_ SX  
WATER WELL PLUGGED W/ \_\_\_\_\_ SX  
CEMENT COMPANY \_\_\_\_\_  
TECHNICIAN \_\_\_\_\_

*Drill pipe stuck @ 1741  
backed off @ 905 still stuck  
1227  
Backed off @ 965"*