

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20220-00-00
Spot: NE Sec/Twnshp/Rge: 17-21S-32W
1320 feet from N Section Line, 1320 feet from E Section Line
Lease Name: GREATHOUSE Well #: 1-17
County: FINNEY Total Vertical Depth: 2705 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2680	0	WITH 550 SX CMT
SURF	8.625	367		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/24/2014 2:30 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 200# HULLS & 100 SX CMT. DISPLACE WITH WATER TO 1300'. TEST CASING TO 700#. RUN CBL & DETERMINE TOC. PERFORATE AND/OR RUN TBG AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/24/2014 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 200# HULLS & 100 SX CMT DOWN THE 4 1/2" CASING. DISPLACE TO 1300' WITH WATER. TEST CASING TO 700#. HOLDING. RUN CBL. FOUND TOC ON OUTSIDE OF 4 1/2" @ 606'. PERFORATE 4 HOLES AT 400'. RUN TBG TO 1313'. CIRCULATE CMT TO SURFACE UP 2 3/8" X 4 1/2" ANNULUS THEN CIRCULATE CMT FROM 400' TO 0' IN 4 1/2" X 8 5/8" ANNULUS USING A TOTAL OF 200 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2661	2671		

Received
KANSAS CORPORATION COMMISSION
AUG 13 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed Ken Jehlik
8-24-14 (TECHNICIAN)

RECEIVED
JUL 30 2014
KCC DODGE CITY

ST