

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22524-00-00
Spot: NENWSWE Sec/Twnshp/Rge: 21-18S-28W
1037 feet from S Section Line, 2104 feet from E Section Line
Lease Name: SHAPLAND TRUST Well #: 1-21
County: LANE Total Vertical Depth: 4625 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	263		WITH 175 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/13/2014 12:00 AM
Plug Co. License No.: 33935 Plug Co. Name: H. D. DRILLING, LLC
Proposal Rcvd. from: LOU TRESNER Company: H. D. DRILLING, LLC Phone: (785) 256-2419

Proposed Plugging Method: 1ST PLUG AT 2170' WITH 50 SX CMT. 2ND PLUG AT 1340' WITH 80 SX CMT. 3RD PLUG AT 690' WITH 40 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 07/13/2014 2:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

1ST PLUG AT 2170' WITH 50 SX CMT. 2ND PLUG AT 1340' WITH 80 SX CMT. 3RD PLUG AT 690' WITH 40 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

KCC WICHITA
JUL 24 2014
RECEIVED

District: 01

Signed Michael Maier
8.14.14 CKM (TECHNICIAN)

RECEIVED

JUL 18 2014

KCC DODGE CITY