

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22531-00-00
Spot: SWSESESE Sec/Twnshp/Rge: 20-18S-27W
134 feet from S Section Line, 347 feet from E Section Line
Lease Name: EM STANLEY UNIT Well #: 1-20
County: LANE Total Vertical Depth: 4644 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 262 | | WITH 165 SX CMT |

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/05/2014 2:30 AM
Plug Co. License No.: 33935 Plug Co. Name: H. D. DRILLING, LLC

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 1ST PLUG AT 2100' WITH 50 SX CMT. 2ND PLUG AT 1260' WITH 80 SX CMT. 3RD PLUG AT 630' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 08/05/2014 4:30 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

1ST PLUG AT 2100' WITH 50 SX CMT. 2ND PLUG AT 1260' WITH 80 SX CMT. 3RD PLUG AT 630' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Received
KANSAS CORPORATION COMMISSION

AUG 13 2014

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY OILWELL.

Plugged through: DP

District: 01

Signed _____

(TECHNICIAN)

8-14-14 CKM

RECEIVED
AUG - 8 2014
KCC DODGE CITY

Form CP-2/3