

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20267-00-00
Spot: N2NWNW Sec/Twnshp/Rge: 8-20S-33W
510 feet from N Section Line, 660 feet from W Section Line
Lease Name: GRUBEN Well #: 1-B
County: SCOTT Total Vertical Depth: 4760 feet

Operator License No.: 5210
Op Name: LEBSACK OIL PRODUCTION INC.
Address: PO BOX 354
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1250		
CIBP		4300		WITH 2 SX CMT
CIBP		4600		WITH 2 SX CMT
PROD	5.5	4759	0	WITH 180 SX CMT
SURF	8.625	417		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/23/2014 10:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: BERT MASTIN Company: LEBSACK OIL PRODUCTION Phone: (620) 276-3442

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/23/2014 4:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 4600' WITH 2 SX CMT. SET CIBP @ 4300' WITH 2 SX CMT. SET CIBP @ 1250' & TEST CASING TO 700 PSI. PERFORATE AT 1200' & SQUEEZE 80 SX CMT. PERFORATE AT 430' & PUMP 160 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4371	4691		

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 06 2014

CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED

JUL 28 2014

KCC DODGE CITY

Signed

8.14.14 CKM

(TECHNICIAN)