

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-00119-00-01
Spot: SWSWNEW Sec/Twnshp/Rge: 35-32S-31W
4031 feet from S Section Line, 3893 feet from E Section Line
Lease Name: SAUNDERS A Well #: 1
County: SEWARD Total Vertical Depth: 6078 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 5100
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4434		WITH 2 SX CMT
CIBP		4650		
PROD	4.5	5590	2503	
SURF	8.625	2437		WITH 850 SX CMT

Well Type: SWD UIC Docket No: D27613.0 Date/Time to Plug: 07/23/2014 8:30 AM
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.
Proposal Rcvd. from: TIMOTHY WALLACE Company: Phone: (405) 203-4921

Proposed Plugging Method: CIBP @ 4434' WITH 2 SX CMT. PLUG AT 2470' WITH 15 SX GEL & 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: NONE
Date/Time Plugging Completed: 07/23/2014 2:30 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

CIBP @ 4434' WITH 2 SX CMT. 1ST PLUG AT 2470' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 550' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4484	4540		

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 05 2014

Remarks: USED 60/40 POZMIX 4% GEL BY KIVETT PLUGGING.

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed

[Signature]
CC: UIC
8.14.14 ckm
(TECHNICIAN)

RECEIVED
JUL 28 2014
KCC DODGE CITY

Form CP-2/3