

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21568-00-00
Spot: W2W2NE Sec/Twnshp/Rge: 21-23S-9W
1320 feet from N Section Line, 2310 feet from E Section Line
Lease Name: WILT Well #: 1-21
County: RENO Total Vertical Depth: 3780 feet

Operator License No.: 9152
Op Name: MAREXCO, INC.
Address: 3033 NW 63RD ST - STE 151
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3774	1810	175 SX
PROD	4.5	3780		220 SX
SURF	8.625	228		200 SX
T1	2.875	3707		

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 07/30/2014 12:00 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: JAMIE Company: MIKE'S TESTING & SALVAGE, INC Phone: _____

Proposed Plugging Method: SAND TO 3600' & 4 SXS. REC PIPE. 35 SXS @ 1350', 35 SXS @ 900', CIRC 260'.

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: PARTIAL

Date/Time Plugging Completed: 07/30/2014 4:00 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SANDED BACK PERFS TO 3605 & CAPPED WITH 4 SXS CEMENT. RECOVERED 1810' OF 4 1/2" CASING. PULLED CASING TO 1340' SPOTTED 35 SXS CEMENT. TAG @ 1210'. PULLED CASING TO 900' TAGGED AT 810'. PULLED CASING TO 260 & CIRCULATED CEMENT TO SURFACE WITH 125 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
3686	3692	CSG	

KCC WICHITA
AUG 08 2014
RECEIVED

Remarks: COPELAND ACID & CEMENT

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

8-14-14 ccm

JK