

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-141-20447-00-00
Spot: NWNWSWSE Sec/Twnshp/Rge: 35-9S-13W
1100 feet from S Section Line, 2465 feet from E Section Line
Lease Name: PECK Well #: 1
County: OSBORNE Total Vertical Depth: 3341 feet

Operator License No.: 5610
Op Name: BRUCE OIL COMPANY, L.L.C.
Address: 1704 LIMESTONE RD
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3341		200 SX
SURF	8.625	729		400 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/05/2014 12:30 PM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: LEVI KOEHN Company: BRUCE OIL CO., LLC Phone: (620) 241-2938

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 7 sx gel and 200 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/05/2014 7:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1650', 1075' and 720'. Ran tubing to 2850' and pumped 7 sx gel followed by 50 sx cement. Pulled tubing to 1675' and pumped 75 sx cement. Fluid circulating out braden head and back side. Pulled tubing to 925' and pumped 150 sx cement. Circulated out both backside and braden head. POOH. Hooked to casing and pumped 10 sx cement. Cement circulated out braden head. Shut in.

GPS: 39.22372 -098.74089

Perfs:

Top	Bot	Thru	Comments
3246	3251		
3231	3238		
3207	3210		
3201	3203		
2919	2923		

Remarks: QUALITY CEMENTING TICKET # 530

Plugged through: TBG

District: 04

Signed Ray ADinkel
8.15.14 CKM (TECHNICIAN) cm

Received
KANSAS CORPORATION COMMISSION

AUG 14 2014

CONSERVATION DIVISION
WICHITA, KS

AUG 07 2014