

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-08221-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 3-9S-16W
330 feet from N Section Line, 330 feet from W Section Line
Lease Name: GAMBLE Well #: 8
County: ROOKS Total Vertical Depth: 1970 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3364		150 SX
SURF	8.625	227		190 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2014 9:30 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CARMEN SCHMITT Phone: (620) 793-5100

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: PARTIAL
Date/Time Plugging Completed: 07/25/2014 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 1800', 1230' and 800'. Ran tubing to 2400' and pumped 100 sx cement w/250 # hulls. Pulled tubing to 1796' and pumped 50 sx cement w/150 # hulls. Pulled tubing to 1486' and pumped 75 sx cement. Pulled tubing to 866' and pumped 70 sx cement w/100 # hulls. Cement circulated to surface. Pulled all tubing. Hooked to 5 1/2" casing and pumped 20 sx cement. Shut in pressure 200 psi. Hooked to 8 5/8" x 5 1/2" annulus and pumped 10 sx cement. Shut in pressure 200 psi.

GPS: 39.30633N -099.10299W

Perfs:

Top	Bot	Thru	Comments
3060	3296		

Received
KANSAS CORPORATION COMMISSION

Remarks: COPELAND ACID AND CEMENTING TICKET # 42654

Plugged through: TBG

AUG 14 2014
CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed _____

Pat Bedore

8-15-14 CKM

(TECHNICIAN)

CM

AUG 06 2014

Form CP-2/3