

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00860-00-00
Spot: SENENE Sec/Twnshp/Rge: 35-12S-22W
906 feet from N Section Line, 448 feet from E Section Line
Lease Name: OGALLAH UNIT Well #: 12-3
County: TREGO Total Vertical Depth: 4002 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3973		125 SX
SURF	13	198		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/04/2014 3:30 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: D S & W WELL SERVICING, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Open hole from 3987' - 4002'
Shot perforations at 930'
Junk stuck in hole at 1907'. Can not get out and can not drill out.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/04/2014 7:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1907' and pumped 275 sx cement w/100 # hulls. Good circulation of cement.
Pulled tubing. Tied on to casing and squeezed w/125 sx cement. Shut in pressure 100 psi.
Tied on to back side and squeezed w/60 sx cement. Shut in pressure 150 psi.

GPS: 39.96859 -099.72507

Perfs:

Remarks: COPELAND CEMENT TICKET # 42660

Plugged through: TBG

Received
KANSAS CORPORATION COMMISSION

AUG 14 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed

8-15-14 CKM

(TECHNICIAN)

CM