

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-033-21463-00-00
Spot: S2NESENE Sec/Twnshp/Rge: 4-35S-16W
1898 feet from N Section Line, 330 feet from E Section Line
Lease Name: LEO Well #: 1-4
County: COMANCHE Total Vertical Depth: 5500 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5218		WITH 2 SX CMT
PROD	4.5	5438	2443	WITH 200 SX CMT
SURF	8.625	1034		WITH 500 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/12/2014 1:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 5218' WITH 2 SX CMT. PLUG AT 1070' WITH 10 SX GEL & 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: NONE
Date/Time Plugging Completed: 08/12/2014 2:30 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

SET CIBP @ 5218' WITH 2 SX CMT. 1ST PLUG AT 1087' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 256' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5314	5321		
5296	5310		
5282	5291		
5268	5276		

Received
KANSAS CORPORATION COMMISSION
AUG 15 2014
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Nathan Willis
(TECHNICIAN)

8-15-14 CKM

RECEIVED
AUG 12 2014
KCC DODGE CITY