

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20209-00-00  
Spot: SE Sec/Twnshp/Rge: 28-21S-32W  
1320 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: LANDGRAF D Well #: 1-28  
County: FINNEY Total Vertical Depth: 2720 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, INC.  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2720	0	WITH 550 SX CMT
SURF	8.625	368		WITH 275 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/24/2014 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 100 SX CMT & 200# HULLS. DISPLACE WITH WATER TO 1200'. TEST CASING TO 700#. RUN CBL TO FIND TOC. PERFORATE AND/OR RUN TBG AS REQUIRED.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/24/2014 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 200# HULLS & 140 SX CMT DOWN 4 1/2" CASING. DISPLACE WITH 3 BBLS WATER TO 200' & PRESSURE TO 700#. HOLDING. RAN CBL THROUGH WET CEMENT SLURRY. TOC IN ANNULUS AT 714'. PERFORATE 4 HOLES AT 400'. CIRCULATE CMT TO SURFACE USING 90 SX CMT, LEAVING THE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2688	2698		

Received  
KANSAS CORPORATION COMMISSION  
**AUG 15 2014**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

*Ken Jehlik*  
(TECHNICIAN)  
8-15-14 CKM

RECEIVED  
JUL 30 2014  
KCC DODGE CITY

Form CP-2/3