

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19309-00-00
Spot: NWNWNWNW **Sec/Twnshp/Rge:** 11-9S-19W
295 feet from N Section Line, 324 feet from W Section Line
Lease Name: HENDERHORST **Well #:** 3
County: ROOKS **Total Vertical Depth:** 3491 feet

Operator License No.: 3553

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6	3479		300 SX
SURF	13.375	251		400 SX

Op Name: CITATION OIL & GAS CORP.

Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 07/29/2014 11:00 AM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Recd. from: NEIL PFANANSTIEL

Company: CITATION OIL AND GAS

Phone: (281) 891-1000

Proposed Squeeze jobs: 294' - 325' w/150 sx cement and 1615' - 1680' w/350 sx cement.

Plugging LKC perforations: 3223' - 3402'

Method: ARB: 3479' - 3491' OH.

Ordered 450 sx 60/40 pozmix 4% gel cement, 14 sx gel and 600 # hulls.

Plugging Proposal Received By: CASE MORRIS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 08/01/2014 2:00 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

07/29/14- Ran tubing to 3450'. Allied pumped 14 sx gel followed by 75 sx cement w/100 # hulls. Pulled tubing to 1700'. Allied pumped 125 sx cement w/400 # hulls. Pulled tubing to 700'. Allied pumped 100 sx cement w/150 # hulls. Cement circulated. PTOH. Topped 6" casing w/35 sx cement. Casing full.

08/01/14- Dug out cement collar and base. Cut casing and surface hanger off. Top of cement 100' down. Topped off 13 3/8" casing w/2.5 yards redi mix.

Perfs:

Top	Bot	Thru	Comments
3479	3491		
3398	3402		
3315	3317		
3304	3312		
3268	3272		
3223	3227		

Remarks: ALLIED


Plugged through: TBG

Received
KANSAS CORPORATION COMMISSION

AUG 14 2014

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed 
8.15.14 CKM (TECHNICIAN)

CM

AUG 14 2014

Form CP-2/3