

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20467-00-03
Spot: NESWNESE Sec/Twnshp/Rge: 23-23S-13W
1940 feet from S Section Line, 700 feet from E Section Line
Lease Name: SODEN Well #: 1
County: STAFFORD Total Vertical Depth: 3915 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3565		
CIBP		3900		
PROD	5.5	3914	1303	WITH 225 SX CMT
SURF	8.625	313		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/01/2014 12:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: JASON SCHULER Company: ABERCROMBIE Phone: (620) 793-8186

Proposed Plugging Method: PUMP 50 SX CMT ON BOTTOM. PLUG AT 760' WITH 10 SX GEL & 50 SX CMT. PLUG AT 340' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/01/2014 1:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 2900' & PUMP 175 SX CMT & 200# HULLS. PULL TBG & WAIT. TAG CMT AT 2300'. CUT CASING & PULL 1303' OF CASING. RUN TBG TO 769' & SPOT 10 SX GEL & 50 SX CMT. PULL TBG TO 338' & SPOT 50 SX CMT. PULL TBG TO 60' & MIXED 60 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3518	3522		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

Received
KANSAS CORPORATION COMMISSION
AUG 15 2014
CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED

AUG - 8 2014

KCC DODGE CITY