

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-21436-00-00  
Spot: NWSW Sec/Twnshp/Rge: 2-19S-21W  
1980 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: RYERSEE L Well #: 1  
County: NESS Total Vertical Depth: 4231 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4217	0	WITH 100 SX CMT
SURF	8.625	331		WITH 250 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/07/2014 12:30 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: RUN BOND LOG TO DETERMINE IF CMT IS ON BACKSIDE OF CASING. IF CMT IS ON BACKSIDE OF CASING PUMP 200# HULLS & ENOUGH CMT TO FILL CASING, THEN 70 SX CMT FOR BACKSIDE. IF NO CMT ON BACKSIDE, PUMP 40 SX CMT ON BOTTOM & 150# HULLS, THEN PERFORATE AT PERMIAN AND PUMP 80 SX CMT OVER CASING VOLUME & 150 SX CMT DOWN BACKSIDE IF IT DOESN'T CIRCULATE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 08/07/2014 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN BOND LOG & FOUND CMT UP IN SURFACE CASING. TIED ONTO CASING & MIXED 300# HULLS IN FIRST BATCH OF CMT. MIXED A TOTAL OF 250 SX CMT DOWN CASING. PRESSURED TO 600# & HELD. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4146	4152		

Received  
KANSAS CORPORATION COMMISSION  
**AUG 15 2014**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed Michael Maier  
8-18-14 CKM (TECHNICIAN)

RECEIVED

AUG - 8 2014

KCC DODGE CITY