

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25792-00-00
Spot: NESWNENE Sec/Twnshp/Rge: 17-18S-21W
975 feet from N Section Line, 975 feet from E Section Line
Lease Name: EHT Well #: 2.17
County: NESS Total Vertical Depth: 4302 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/07/2014 12:30 AM
Plug Co. License No.: 33323 Plug Co. Name: PETROMARK DRILLING, LLC
Proposal Rcvd. from: BRANDON WILLS Company: PETROMARK DRILLING, LLC Phone: (316) 734-8977

Proposed Plugging Method: 1ST PLUG AT 1490' WITH 50 SX CMT. 2ND PLUG AT 720' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 08/07/2014 2:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

1ST PLUG AT 1490' WITH 50 SX CMT. 2ND PLUG AT 720' WITH 80 SX CMT. 3RD PLUG AT 240' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

Received
KANSAS CORPORATION COMMISSION

AUG 15 2014

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED
AUG - 8 2014
KCC DODGE CITY

Signed Michael Maier
8.18.14 CCM (TECHNICIAN)

SP

Form CP-2/3