

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-031-21976-00-00
Spot: SWSE Sec/Twnshp/Rge: 28-22S-16E
660 feet from S Section Line, 1980 feet from E Section Line
Lease Name: ARLIN MEATS Well #: 2
County: COFFEY Total Vertical Depth: 1095 feet

Operator License No.: 4567
Op Name: D. E. EXPLORATION, INC.
Address: PO BOX 128
WELLSVILLE, KS 66092

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1087		138 SX
SURF	8.375	43		59 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/29/2014 2:00 PM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: HARVEY FRANCIS Company: _____ Phone: (620) 365-9704

Proposed Plugging Method: Run 1" to TD, wash throug 1", then fill with cement through 1" from bottom to top. Well not perforated.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 07/29/2014 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report: _____ Perfs: _____

RUN 1" TO 1000' PUMPED 25 SXS CEMENT TO SURFACE,PULL 1" OUT.

RECEIVED
AUG 11 2014
KCC Chanute Dist. #3
MH

Received
KANSAS CORPORATION COMMISSION

Remarks:

Plugged through: TBG

AUG 14 2014
CONSERVATION DIVISION
WICHITA, KS

District: 03

Signed Mike Heffern
8-18-14 (TECHNICIAN)

Hurricane Services, Inc.
 3613 A Y Road
 Madison, KS 66860
 Office # 620-437-2661
 Brad Cell # 620-437-6765



HURRICANE SERVICES INC
 OILFIELD SERVICES
 MADISON, KANSAS

API# 15-031-21976
 Ticket Number 100512 21978
 Location Madison
 Foreman Brad Butler

Copy for Mike Heffernan # API. 15-031-21975

Cement Service ticket

Date	Customer #	Well Name & Number	Sec./Township/Range	County
7-29-14		Arland Meats #2	28-22-16	Coffey
Customer D.E. Exploration		Mailing Address	City	State Zip

Job Type:	Truck #	Driver
Plug To Abandon	201	Jerry
Hole Size:	Casing Size:	Displacement:
Hole Depth:	Casing Weight:	Displacement PSI:
Bridge Plug:	Tubing: 2 7/8"	Cement Left in Casing:
Packer:	PBTD:	

Quantity Or Units	Description of Services or Product	Pump charge	
0	Mileage Truck in Area	\$3.25/Mile	N/C
25 SACKS	60/40 Pozmix cement	12.00	300.00
85 lbs.	Gel 4%	.30	25.50
1/2 Hrs.	WATER TRUCK < 3:00 To 4:30 >	84.00	126.00
Tons	Bulk Truck 3 rd well of 3		100.00
	Plugs		
		Subtotal	1151.50
		Sales Tax 6.15%	20.02
		Estimated Total	1171.52

Remarks: Note: Rig up to 1" Pipe at 1000', Break circulation. Mixed Cement Till we had good cement returns. Pull 1" Pipe out of well, fill 2 7/8" Tubing back up with cement. Well cemented solid from 1000' to surface with 25 sks cement

Received
 KANSAS CORPORATION COMMISSION

AUG 14 2014

"Thank you"

CONSERVATION DIVISION
 WICHITA, KS

Note: Well Had never been Performed

Witnessed by Hervey
 Customer Signature