

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20373-00-00  
Spot: NWNWSWNE Sec/Twnshp/Rge: 33-26S-31W  
3950 feet from S Section Line, 2626 feet from E Section Line  
Lease Name: BETTY RANDLE Well #: 1  
County: FINNEY Total Vertical Depth: 2800 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2796	0	WITH 350 SX CMT
SURF	8.625	565		WITH 300 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/01/2014 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: TRACEY HOLLIS Company: HERMAN L LOEB Phone: (719) 340-8987

Proposed Plugging Method: PUMP 100 SX CMT WITH 200# HULLS IN FIRST 20 SX CMT. DISPLACE WITH WATER TO 1100' +/- . PRESSURE UP & TEST CASING TO 700#. RUN CBL TO DETERMINE TOC. PERFORATE AND/OR RUN TBG AS REQUIRED. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/01/2014 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 100 SX CMT WITH 200# HULLS DOWN 4 1/2" CASING. DISPLACE WITH WATER TO 1500'. HOLE LOADED & STAYED FULL. RUN CBL FROM 1400' TO 15'. TOC @ 170'. RUN TBG TO 1110' & CIRCULATE CMT TO SURFACE WITH 100 SX CMT. TOOH WITH TBG & TOP OFF CASING WITH 30 SX CMT. FILL THE ANNULUS WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2672	2682		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

Received  
KANSAS CORPORATION COMMISSION

AUG 15 2014

CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed \_\_\_\_\_

8-18-14 *Ken Jehlik*

(TECHNICIAN)

RECEIVED

AUG -7 2014

KCC DODGE CITY