

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-00522-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 31-5S-20W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: PINKERTON A Well #: 2  
County: PHILLIPS Total Vertical Depth: 3628 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3611		100 SX
SURF	10.75	179		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/22/2014 8:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: RICK HOCKMAN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Open hole: 3611' - 3628'  
Ordered 480 sx 60/40 pozmix 4% gel cement, 17 sx gel and 900 # hulls.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/22/2014 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes each at 1770' and 1150'. Ran tubing to 3612'. Swift Services pumped 17 sx gel followed by 100 sx cement w/300 # hulls. Pulled tubing to 1887'. Swift pumped 150 sx cement w/300 # hulls. Pulled tubing to 945'. Swift pumped 160 sx cement w/300 # hulls. Cement circulated. PTOH. Topped 7" casing w/10 sx cement. Casing is full. Hooked up to surface pipe and pumped 60 sx cement. Shut in pressure 150 psi.

Perfs:

Top	Bot	Thru	Comments
3611	3628		

Received  
KANSAS CORPORATION COMMISSION

Remarks: SWIFT SERVICES TICKET # 26730

JUL 31 2014

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 04

Signed Richard Williams  
8-18-14 CKM (TECHNICIAN)

CM

JUL 25 2014