

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-00605-00-00
Spot: SWSESE Sec/Twnshp/Rge: 32-5S-20W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: RAY A Well #: 3
County: PHILLIPS Total Vertical Depth: 3537 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3525		100 SX
SURF	8.625	155		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/21/2014 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: RICK HOCKMAN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Open hole: 3525' - 3537'.
Plugging Casing leaks: 2745' - 2865', 2145' - 2275' and 120' - 150'.
Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/900 # hulls.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/21/2014 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated 2 holes each at 1671' and 1080'. Ran tubing to 3423'. Swift services pumped 100 sx cement w/300 # hulls. Pulled tubing to 2425' and pumped 110 sx cement w/300 # hulls. Pulled tubing to 1400' and pumped 140 sx cement w/300 # hulls. Cement circulated. PTOH. Tied on to 5 1/2" casing and pumped 45 sx cement. Circulated cement out 8 5/8" surface casing.

Perfs:

Top	Bot	Thru	Comments
3525	3537		

Received
KANSAS CORPORATION COMMISSION

Remarks: SWIFT SERVICES TICKET # 26729

Plugged through: TBG

JUL 31 2014
CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Richard Williams
8.18.14 CKM (TECHNICIAN) CM

JUL 25 2014