

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21722-00-00
Spot: SWSENWNE Sec/Twnshp/Rge: 4-22S-23W
1039 feet from N Section Line, 1780 feet from E Section Line
Lease Name: PHILLIPS-DENNY Well #: 1-4
County: HODGEMAN Total Vertical Depth: 4700 feet

Operator License No.: 31652
Op Name: NORSTAR PETROLEUM, INC.
Address: 88 INVERNESS CIR E. UNIT F104
ENGLEWOOD, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1582		CEMENTED TO SURFACE
PROD	4.5	4699	0	WITH 100 SX CMT
SURF	8.625	257		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/24/2014 9:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DAVE PAULY Company: NORSTAR PETROLEUM Phone: (316) 250-2045

Proposed Plugging Method: TOP FISH @ 2725'. RUN TBG TO 2725' & PUMP 25 SX CMT. PLUG AT 1800' WITH 100 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: PARTIAL
Date/Time Plugging Completed: 07/24/2014 12:05 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

COMPANY TRIED UNSUCCESSFULLY FOR 30 DAYS TO FISH BROKEN TBG & RETRIEVABLE BRIDGE PLUG. TOP OF FISH @ 2725'. RAN TBG TO 2715' & PUMPED 25 SX CMT WITH 200# HULLS. 1ST PLUG AT 1811' WITH 100 SX CMT. 2ND PLUG AT 315' WITH 50 SX CMT. 3RD PLUG AT 63' WITH 10 SX CMT. TIED ONTO BACKSIDE & PRESSURED TO 500# WITH 0 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4564	4571		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

AUG 05 2014

CONSERVATION DIVISION
WICHITA, KS

District: 01

Signed [Signature]
8.18.14 ckm (TECHNICIAN)

RECEIVED
JUL 25 2014
KCC DODGE CITY

Form CP-2/3