

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22688-00-00  
Spot: NESENWSE Sec/Twnshp/Rge: 36-32S-15W  
1808 feet from S Section Line, 1343 feet from E Section Line  
Lease Name: CARR Well #: 1-A-36  
County: BARBER Total Vertical Depth: 5140 feet

Operator License No.: 32811  
Op Name: OSAGE RESOURCES, LLC  
Address: 6209 N K61 HWY  
HUTCHINSON, KS 67502

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1220		
CIBP		2220		WITH 2 SX CMT
CIBP		2336		
CIBP		2650		
CIBP		4750		
PROD	5.5	5140	0	WITH 275 SX CMT
SURF	8.625	350		WITH 300 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/25/2014 9:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: JD DUBWIG Company: OSAGE RESOURCES Phone: (620) 664-9622

Proposed  
Plugging  
Method:

SET CIBP @ 2220' WITH 2 SX CMT. PERFORATE AT 900'. PUMP DOWN 5 1/2" CASING WITH CMT  
CIRCULATING CMT TO SURFACE & FILLING 5 1/2" CASING WITH CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/07/2014 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 2220' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PRESSURE TEST CASING TO 150#. LEAKED OFF. SET CIBP @ 1220'. PRESSURE TEST CASING TO 300#. HELD. MIXED & PUMPED 350 SX CMT. ESTABLISHED RETURNS 40 BBLS INTO JOB. HAD GOOD RETURNS THROUGH OUT BUT CMT DID NOT CIRCULATE. SHUT DOWN TO LET CMT SET. 7/26/14: FOUND TOC @ 186'. 8/7/14: TOPPED OF HOLE WITH 3 YDS OF PORTLAND CMT.

Perfs:

Top	Bot	Thru	Comments
4798	4800		

Received  
KANSAS CORPORATION COMMISSION  
**AUG 15 2014**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED

AUG 12 2014

KCC DODGE CITY

Signed

8-18-14 *clm*

(TECHNICIAN)

*SP*