

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-21081-00-00  
Spot: SWSENWNW Sec/Twnshp/Rge: 23-20S-33W  
1040 feet from N Section Line, 729 feet from W Section Line  
Lease Name: BAUER-BUCKNER Well #: 1  
County: SCOTT Total Vertical Depth: 4950 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH ST  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217		WITH 165 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/22/2014 9:30 AM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: WILLY WYNN Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2100' WITH 50 SX CMT. 2ND PLUG AT 1230' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE  
Date/Time Plugging Completed: 07/22/2014 11:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 2100' WITH 50 SX CMT. 2ND PLUG AT 1230' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

RECEIVED  
KANSAS CORPORATION COMMISSION


Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

**AUG 05 2014**

Plugged through: DP

CONSERVATION DIVISION  
WICHITA, KS

District: 01

Signed   
8-18-14 CCM (TECHNICIAN)

RECEIVED  
JUL 29 2014  
KCC DODGE CITY